

**NOTES:**

- 1) The Project Engineer will flag the limits of tree clearing for the contractor prior to beginning of work.
- 2) Any merchantable timber may be harvested and removed at the contractors expense. All other cleared material will be placed in piles and burned and buried within the limits of the cleared area. No material may be burned and buried within 100' of a river channel or other wetland feature. If possible, stumps should be removed prior to piling and burning to facilitate a more complete burn and then all unburned material buried in place.



Buffalo County

Clear & grub all woody vegetation.  
(Approx 10 acres)


Burn & bury stumps & debris.  
(Approx 10 piles)

Clear & grub all woody vegetation.  
(Approx 6 acres)

Burn & bury stumps & debris.  
(Approx 6 piles)

**Legend**

- Property Boundary
- CLEAR & GRUB
- DOWNFALL CLEANUP



PROJECT NO. 24-011		
Tract 2024002		
TREE REMOVAL		
SHEET NO: 3 of 3	DATE: 8/19/24	DRAWN BY: TRT